

## Contents

1.	INTRODUCTION .....	2
2.	DEFINITIONS AND ACRONYMS .....	4
3.	OPERATIONS .....	4
3.1	Facility Descriptions.....	4
3.1.1	Reservoir and Dam .....	4
3.1.2	Spillway .....	5
3.1.3	Diversion Ditch System.....	5
3.1.4	RTP Head Tank and Plumbing System.....	6
3.1.5	Storm Water Pond Discharge Pipeline .....	6
3.1.6	Seepage Collection Wells.....	6
3.2	Storage Objective and Control of RTP .....	8
3.3	Monitoring .....	9
3.3.1	Reservoir Water Elevation and Volume .....	9
3.3.2	Seepage Collection Wells Pump-up Rate.....	9
3.3.3	Flow Rate from Drystack Tailings Facility Flow-through Drain .....	9
3.3.4	Liese Creek Flow Downstream of Seepage Collection Wells.....	9
3.3.5	Dam Crest Elevation.....	9
3.3.6	Groundwater Monitoring Wells.....	9
3.3.7	Meteorological Stations .....	10
4.	MAINTENANCE.....	15
4.1	Dam and Abutments.....	15
4.2	Spillway .....	15
4.3	Diversion Ditch .....	15
4.4	Seepage Collection Wells .....	15
4.5	RTP Pumps, Head Tank and Affiliated Facilities .....	15
4.6	Liese Creek Flumes.....	16
5.	INSPECTION.....	16
5.1	Daily Inspection.....	16
5.2	Weekly Inspection.....	16
5.3	Monthly Inspection .....	16
5.4	Periodic Safety Inspection .....	16
6.	EXERCISES.....	16
6.1	Orientation Exercise.....	16
6.2	Table-top Exercise.....	16
7.	UNUSUAL OCCURENCES .....	17
7.1	Earthquake.....	17
7.2	Extreme Precipitation .....	17
7.3	High Water Level.....	17
8.	RELATED DOCUMENTS.....	17
9.	REFERENCES .....	17
10.	APPENDICES.....	17
10.1	APPENDIX I – Pogo Dam Project Data Sheet.....	18
10.2	APPENDIX II – Weekly and Monthly Inspection Forms .....	20
10.3	APPENDIX III - Drawings.....	23

Prepared by:	James Meyers	Document Status:	Uncontrolled	Document No:	PGO-ENV-008-MAN
Approved by:	Senior Environmental Coordinator	Review Date:	7 Jul 2023	Revision No:	8
		Approver's Signature:	James Meyers	Issue Date:	13 Oct 2023
				Page No:	1

## 1. INTRODUCTION

Northern Star (Pogo) LLC is the operator of the Pogo gold mine, located 38 miles northeast of Delta Junction, Alaska.

The Pogo Recycle Tailings Pond (RTP) Dam (NID ID#AK00304) was constructed in 2004/2005. The Pogo RTP Dam is a lined rockfill structure constructed to provide storage of seepage and runoff water from the Drystack Tailings Facility (DSTF), treated mine drainage, and surface runoff from other facilities. Water from the reservoir is used in the mining and milling process or treated and discharged.

The Pogo RTP Dam was approved to operate as a Class II (significant) hazard potential dam as defined in 11 AAC 93.157 on May 25, 2006. The first Periodic Safety Inspection (PSI) was conducted in 2007 and the certificate of approval to operate a dam was renewed on December 31, 2007. During the second PSI in 2010, Alaska Department Natural Resources (ADNR) pointed out that the dam break analysis carried out in 2001/2002 failed to evaluate the risk of inundation into the underground working area at the 1875 Portal and 1690 Portal and the influences on the Goodpaster River recreational cabins. Subsequently, ADNR decided to change the hazard potential class of Pogo RTP Dam from Class II to Class I (high).

Pogo conducted a new dam break analysis in April 2011 and it concluded that a hypothetical breach of the dam would lead to significant flooding in underground at the 1875 Portal and 1690 Portal. However, there is no expectation for inundation at the cabins along the Goodpaster River. This analysis endorsed the hazard potential class I for the Pogo RTP Dam. A revision to the dam break analysis hydrologic model was performed in 2023 in order to reassess the impacts of flooding on additional development within Liese Creek valley.

A third PSI was conducted on June 18, 2013. It concluded that the RTP Dam generally appeared to be in good condition, but it was recommended to re-evaluate the hydrology and hydraulic modeling for the Probable Maximum Flood (PMF) to account for the new diversion ditch and the reduced capacity of Flume #1 and to verify the effect on the RTP Dam spillway.

A fourth PSI was conducted on June 14, 2016. The PSI Report for this inspection concludes that the RTP Dam is generally in good condition. The report recommends studying a potential grouting program at the southern flow path identified by Willowstick (2011); minor repairs to SD Flume #1; standardization of dam survey methodology, development of action level thresholds for dam settlement; updates to the Operation and Maintenance (O&M) manual related to RTP Head Tank #2; and updates to the O&M Manual to produce action levels and contingencies for: possible overtopping of the diversion ditch and flumes in the O&M Manual, SCW performance, and LC Flume #2 conditions.

A fifth PSI was conducted from July 9-11, 2019. The PSI Report for this inspection concludes that the RTP Dam is in "*satisfactory condition*" as defined by the National Inventory of Dams (NID) Data Dictionary. "*Satisfactory*" is the highest level of condition assessment defined by the NID Data Dictionary. The report recommends quality control for survey of the dam crest; DSTF piezometer connection to a data center by telemetric methods; evaluation of mitigation options to reduce the potential of dam crest overtopping by wave action from a cost and risk perspective; bi-monthly flume inspections; grouting repair between the Flume #1 concrete structure and surrounding ground; current liquefaction assessment on the overburden soils in the foundation of the dam and for the DSTF; and removal of debris and vegetation from diversion ditches and South Diversion Ditch Flume #1.

A sixth PSI was conducted from June 28-29, 2022. The PSI Report for this inspection concludes that the RTP Dam is in "*satisfactory condition*" as defined by the National Inventory of Dams (NID) Data Dictionary. "*Satisfactory*" is the highest level of condition assessment defined by the NID Data Dictionary. The report recommends the RTP Dam should continue to be given a Class I hazard potential classification due to the potential flooding of the downstream mine portals. Further recommendations provided in the PSI Report are as follows:

- Remove all woody vegetation and other vegetation that obscures, obstructs, or prevents access to the

Prepared by:	James Meyers	Document Status:	Uncontrolled	Document No:	PGO-ENV-008-MAN
		Review Date:	7 Jul 2023	Revision No:	8
Approved by:	Senior Environmental Coordinator	Approver's Signature:	James Meyers	Issue Date:	13 Oct 2023
				Page No:	2

# RECYCLING TAILINGS POND OPERATING AND MAINTENANCE MANUAL

dam slopes and abutment contacts, extending at least 20 feet past the limit of dam fill, spillway, flumes (both conveyance and monitoring), diversion ditches, seepage collection wells (SCW), and toe of the Dry Stack Tailings Facility that lies upstream of the dam.

- Install concrete crack monitors/gauges over cracks in the reinforced concrete spillway to allow for simple quantitative tracking of cracks over time.
- Remove organic matter, debris, and accumulated sediment from the diversion ditches, still basins, flume inlets, spillway, and flumes.
- Investigate the characteristics and potential source of sediment accumulating around Liese Creek Flume #1 and develop a plan for removal (if necessary) and source control.
- Repair the stilling basin for the weir monitor on the Liese Creek Flume #1 and the level meter for SCW #5.
- Review the seismic stability of the RTP Dam using modern analysis techniques (i.e., Bray and Macedo 2019).

Outstanding recommendations from the 2022 PSI will be addressed in 2023-2024.

To expand the capacity of DSTF from the originally approved, 7.5Mt to 20Mt, a new diversion ditch consisting of 5,800 ft-long north ditch and 2,650 ft-long south ditch was constructed approximately 150 ft above the original diversion ditches. The current diversion ditches utilize the original ditches below the DSTF to bypass the reservoir of the RTP Dam. The construction work commenced in April 2012 and was completed in September 2013. A recent volumetric optimization study indicated that the capacity of the DSTF can be increased by approximately 3.3 million cubic yards while remaining below the elevation of the current diversion ditches. The expansion project will allow for compacted tailings and waste rock to be deposited below the current diversion ditch configurations. Consequently, the contributing areas and respective hydrology parameters for the dam will not change and the operation of the RTP Dam will not be affected. Engineering evaluations confirm that the DSTF remains stable with the additional load.

The purpose of this O&M Manual is to describe operating and monitoring procedures for the dam and reservoir under normal and unusual conditions, and to provide guidance and procedures for monitoring, maintenance, and routine inspection for the Pogo RTP Dam.

Prepared by:	James Meyers	Document Status:	Uncontrolled	Document No:	PGO-ENV-008-MAN
		Review Date:	7 Jul 2023	Revision No:	8
Approved by:	Senior Environmental Coordinator	Approver's Signature:	James Meyers	Issue Date:	13 Oct 2023
				Page No:	8

## 2. DEFINITIONS AND ACRONYMS

AAC	Alaska Administrative Code
ADEC	Alaska Department of Environmental Conservation
ADNR	Alaska Department of Natural Resources
APDES	Alaska Pollutant Discharge Elimination System
DCS	Data Communication System
DSTF	Drystack Tailing Facility
EAP	Emergency Action Plan
EDMS	Environmental Data Management System
HDPE	High Density Polyethylene
LC	Liese Creek
MET	Meteorological Station
MGal	Million Gallons
MWTP	Mine Water Treatment Plant
ND	North Ditch
NID	National Inventory of Dams
ORTW	Off-River Treatment Work
O&M	Operations and Maintenance
PMF	Probable Maximum Flood
PSI	Periodic Safety Inspection
RTP	Recycle Tailing Pond
SCW	Seepage Collection Well
SD	South Ditch
SWPPP	Stormwater Pollution Prevention Plan
USGS	United States Geological Survey
WAD	Weak Acid Dissociable

## 3. OPERATIONS

### 3.1 Facility Descriptions

#### 3.1.1 Reservoir and Dam

**Figure 1** shows the facility location map for RTP Dam and the relevant facilities including the diversion ditch and Storm Water Pond.

The Pogo RTP Dam has a storage capacity of approximately 43.4 million gallons (Mgal). The Pogo RTP Dam is permitted for a crest elevation of 2,092 feet above mean sea level (amsl) which, as designed, results in a 40 Mgal capacity. The as-built configuration offers about 9% more storage capacity than the design configuration. Due to sedimentation in the pond, water is unable to be drawn below 4.0 Mgal, resulting in a usable volume of 39.4 Mgal for operations purposes.

The Pogo RTP Dam serves as the impoundment where water can be stored prior to recycling or subsequent treatment and discharge to the environment. The Pogo RTP Dam impounds runoff from the DSTF, captures natural flows from the catchment area below the limits of diversion ditch and the DSTF, and collects various plant site contact runoff water. Treated mine water may also be stored in cases when it cannot be discharged into the Goodpaster River as allowed by APDES Permit #AK-0053341.

Prepared by:	James Meyers	Document Status:	Uncontrolled	Document No:	PGO-ENV-008-MAN
Approved by:	Senior Environmental Coordinator	Review Date:	7 Jul 2023	Revision No:	8
		Approver's Signature:	James Meyers	Issue Date:	13 Oct 2023
				Page No:	4

The dam is a membrane lined rockfill embankment with a hydraulic height of 65.7 feet. The dam crest is 35 feet wide and extends over 550 feet. The lined crest elevation is designed to be nominally 2,090 feet amsl; however, it was confirmed that the actual lined crest elevation ranged from 2,088.7 feet amsl to 2,089.4 feet amsl during the second PSI in 2010 by digging five holes at the crest of embankment.

### 3.1.2 Spillway

Located on the left abutment, the spillway intake structure is an 8 foot wide rectangular reinforced concrete structure and discharges into a 6 foot diameter half corrugated steel pipe (CSP). The discharge from the south diversion ditch enters the channel on the downstream slope of the dam. A 20-inch HDPE pipe is connected to a concrete headwall of Flume #1 at the end of south diversion ditch. The 20-inch HDPE pipe transitions into a 10-foot long section of 24-inch CSP with elbow that outfalls into the spillway CSP. The 6-foot diameter half spillway CSP then transitions to 8-foot in diameter. The channel is approximately 600 feet long and subsequently discharges into a rip rap outfall located in a channel that would return flows to Liese Creek in the event of spillway operation.

The elevation of the sharp crested weir located in the spillway inlet is at elevation 2,084 feet amsl. The spillway discharge curve is shown on Drawing A0172-VII-042 in Appendix III. The spillway has a maximum discharge capacity of 440 cubic feet per second (cfs). The construction of new diversion ditch expanded the catchment area from 75.0 acres to 123.9 acres. AMEC estimated the peak outflow with a 24-hour Probable Maximum Precipitation (PMP) event (11 inches rainfall within 24 hours) for pre-expansion conditions. The results were a peak inflow for the RTP of 208 cfs, a discharge for the spillway of 176 cfs, and the maximum RTP elevation of 2087.3 feet amsl. SRK re-evaluated the peak outflow with a 24-hour PMP for post-expansion conditions. The results were a peak inflow for the RTP of 316 cfs, a discharge for the spillway of 279 cfs, and the maximum RTP elevation of 2088.3 feet amsl. Based on a wave height of 1.0 feet and an estimated wave run up of 1.3 feet calculated by AMEC, the reduction in spillway elevation may be required to provide enough freeboard to keep the wave run up below the liner elevation at the dam crest.

AMEC estimated the run-off rate at Flume #1 with 24-hour PMP event, and it was 310 cfs for pre-expansion conditions. AMEC evaluated that Flume #1 had a discharge capacity of 20 cfs with a 20-inch HDPE pipe. The evaluations conducted by SRK and AMEC indicate that the PMF resulting from the PMP could lead to a backup of water within the south diversion ditch and possible overflow into the RTP catchment. They recommended re-evaluation of the hydrology and hydraulic modeling for the PMF to account for the new diversion ditch and the flow capacity of Flume #1 to verify the effect on the spillway.

### 3.1.3 Diversion Ditch System

The diversion ditch system (DDS) intercepts "non-contact" surface water from areas unaffected by mine development upgradient from the DSTF. The DDS includes a channel excavated into the hillside around the perimeter of the DSTF, an adjacent access road, drop inlets at the downstream end, and steep, culvert pipes to direct the flow to the discharge points at the confluence with Liese Creek at the valley floor, downstream of the RTP Dam. The upper portion of the DDS directly adjacent to the DSTF can be abandoned and reconstructed at higher elevations as the DSTF is expanded to accommodate additional tailings from new resources discovered and developed at the Pogo Mine. The DDS was first constructed in 2006 for a nominal DSTF capacity of 7.5 Mt. The DDS was modified in 2012 and 2013 for an increased nominal DSTF capacity of 20 Mt. The current plan to increase the DSTF capacity by 4.3 Mt will not require any modification of the DDS.

The current north diversion ditch is about 5,850 feet long and runs from Inlet 3 at an elevation of 2,750 feet amsl into the existing north diversion ditch at an elevation of about 2,404 feet amsl. The remaining 2,049 feet of original north diversion ditch connects to Flume #2 at an elevation of 2,158 feet amsl. Flume #2 is composed of a 750 feet-long, 60-inch diameter open CSP culvert, which discharges into Liese Creek about 700 feet downstream of the RTP Dam. The discharge capacity of Flume #2 is estimated to be 164 cfs.

The current south diversion ditch is about 2,654 feet long and drops in elevation from about 2,716 to 2,661 feet amsl. The south diversion ditch connects to the original ditch at about elevation 2,499 feet amsl via a 342-foot, 24-inch diameter HDPE pipe with intake and outlet structures. The discharge capacity of New South Flume is estimated to be 27 cfs (SRK, 2013a). The 2,329 feet-long original south diversion ditch connects to Flume #1 at an elevation of 2,195 feet amsl. The water from the south diversion ditch discharges into the RTP dam spillway via a 427-foot, 20-inch diameter HDPE pipe. The discharge capacity of Flume #1 is estimated to be 20 cfs (AMEC, 2006).

The diversion ditch is designed to intercept a one in 200-year, 24-hour precipitation event (4.6 inches within 24 hours). One foot of freeboard was incorporated into the design. The estimated design flow (200-year, 24-hour precipitation event) for 20 Mt DSTF capacity calculated by SRK is 78 cfs at Flume #2 (north diversion

Prepared by:	James Meyers	Document Status:	Uncontrolled	Document No.:	PGO-ENV-008-MAN
Approved by:	Senior Environmental Coordinator	Review Date:	7 Jul 2023	Revision No.:	8
		Approver's Signature:	James Meyers	Issue Date:	13 Oct 2023
				Page No.:	5

ditch), 24 cfs at the New South Flume and 34 cfs at Flume #1 (south diversion ditch), respectively.

### 3.1.4 RTP Head Tank and Plumbing System

During normal operation of the Pogo RTP dam, the pond water is withdrawn by the RTP reclaim pumps located near the upstream toe of the RTP. Two 20-HP six-inch submersible pumps (one for operation and the other for back up), each having a pumping capacity of 600 gpm, are set at 2,020 feet amsl. The reclaim pumps are:

- Manufactured by National Pump Company
- Model Number M14HC
- Motor type HITACHI 20 HP MOTOR (460 V, 3 Phase)

The pond water is sent to RTP Head Tank #1, a 52,000-gallon RTP Head Tank, and RTP Head Tank #2, a 31,000-gallon RTP Head Tank, both located on the right abutment via a 6-inch diameter HDPE pipeline. RTP Water is then sent to Mine Water Treatment Plant 3 (MWTP#3), Mill Plant, or underground working area by gravity flow. The maximum discharge rate is 500 gpm. When the treated mine water cannot be discharged into the Off-River Treatment Works (ORTW), the treated mine water is sent from MWTP#3 to the RTP Head Tank (up to 300 gpm). The schematic plumbing system around the RTP Head Tank is shown on RTP Piping & Instrumentation Diagram Drawing in Appendix III.

### 3.1.5 Storm Water Pond Discharge Pipeline

The Storm Water Pond located near the 1690 portal was constructed to gather the storm water from Mill Bench and Haul Road above Mill Bench. Two pumps are installed at the pond and collected storm water is sent to RTP via a 16-inch HDPE pipeline. The pipeline runs across the downstream dam face, across the top of spillway, and discharges over bedrock above the south-side of the dam and upstream of the spillway inlet. The storm water is pumped up intermittently depending on the weather. The water volume pumped up from Storm Water Pond to the RTP is approximately 0.5 – 1.5 million gallons per year.


### 3.1.6 Seepage Collection Wells

The seepage collection wells (SCWs) are located approximately 400 ft downstream of the RTP. There are currently four deep wells (SCW#5 - 8) and one shallow well (SCW#9) in operation. The SCWs collect groundwater (including any seepage from the RTP) and return it to the RTP Head Tank via a 4-inch HDPE pipeline (Drawing RTP Piping & Instrumentation Diagram). Table 1 provides details on SCWs.

**Table 1: Seepage Collection Well Information**

SCW ID	Manf.	Model	HP	Voltage	Phase	Discharge in.	GPM	Casing in.	Pump Inlet ft.
Well #5	Grundfos	40S50-15	5	460	3	2	25	5	67.50
Well #6	Grundfos	40S50-15	5	460	3	2	25	5	66.75
Well #7	Grundfos	40S50-15	5	460	3	2	25	5	71.00
Well #8	Grundfos	40S50-15	5	460	3	2	25	5	62.75
Well #9	Flygt	BS-2670.180	27	460	3	4	100	20	13

Prepared by:	James Meyers	Document Status:	Uncontrolled	Document No:	PGO-ENV-008-MAN
Approved by:	Senior Environmental Coordinator	Review Date:	7 Jul 2023	Revision No:	8
		Approver's Signature:	James Meyers	Issue Date:	13 Oct 2023
				Page No:	6




Prepared by:	James Meyers	Document Status:	Uncontrolled	Document No:	PGO-ENV-008-MAN
		Review Date:	12 Nov 2022	Revision No:	8
Approved by:	Senior Environmental Coordinator	Approver's Signature:	James Meyers	Issue Date:	14 Dec 2022
				Page No:	7

## 3.2 Storage Objective and Control of RTP


The RTP was originally designed to provide process makeup water for the Mill and underground drilling water. Most underground drilling water is now supplied by the underground water recycling system. Treated mine, RTP, and gravel pond water are the primary sources for process makeup water. Therefore, the RTP storage objective was changed to keeping a minimum volume of water as follows:

- Summer season (June to September): 5 Mgal target. This is enough to supply makeup water to the mill for about 20 days, assuming a water consumption rate of 100 gpm at the Mill. Figure 2 shows the RTP reservoir volume-elevation curve. If the RTP water volume exceeds 5 Mgal (RTP reservoir elevation: 2,042 feet amsl), the RTP water is discharged into MWTP#3, treated and then discharged into ORTW. Figure 3 shows the drawdown curve for 300 gpm discharge from the RTP.
- Winter season (October to May): 15 Mgal target. In order to handle a potential shortage of process makeup water during winter season, the RTP water storage volume is increased to 15 Mgal by the end of October. The water volume is then reduced over the winter to 5 Mgal before the spring breakup or by the end of May.

**Figure 2: RTP volume-elevation curve**



**Figure 3: Drawdown curve for 300 gpm discharge from RTP**



Prepared by:	James Meyers	Document Status:	Uncontrolled	Document No:	PGO-ENV-008-MAN
Approved by:	Senior Environmental Coordinator	Review Date:	7 Jul 2023	Revision No:	8
		Approver's Signature:	James Meyers	Issue Date:	13 Oct 2023
				Page No:	8



## 3.3 Monitoring

Monitoring frequencies are summarized in Table 2. Figure 4 shows the location of monitoring points.

### 3.3.1 Reservoir Water Elevation and Volume

The reservoir elevation is measured by the pressure transducer installed at the RTP reclaim pump station at the bottom of the reservoir. The pressure transducer is connected to the Data Communication System (DCS) and the data are recorded automatically and reported in the "Daily Water Dashboard" issued by the Water Operations Department via email. Personnel can also query the DCS for long-term records as required.

### 3.3.2 Seepage Collection Wells Pump-up Rate

The pump rates of the SCWs are monitored by two flow meters which are connected to the DCS. One flow meter is for SCW#5 - 8, and the other is for SCW#9. Data can be queried from the DCS for long-term records as required.

The pump rates of the SCWs vary by season and can be correlated to RTP water elevation. Historically, the pump rate from SCW#5 - 8 increases from 70 gpm up to 170 gpm in relation to the reservoir elevation. The rate reduced by approximately 50 gpm in 2013 due to grouting conducted in April 2013 (see Figures 5 and 6). SCW#9 dries up when the reservoir elevation is 2,062 feet amsl (RTP volume: 16 Mgal) or lower. Once the reservoir level exceeds 2,062 feet amsl, the pump-up rate from SCW#9 increases up to 80 gpm in proportion to the reservoir elevation (see Figures 5 and 7). SCW#9 remained dry in 2013 even though the reservoir level reached to 2,064 feet amsl in late September. The combined pump up rate from SCW#5 - 8 and SCW#9 historically ranges between 70 gpm and 340 gpm under normal operating conditions.

### 3.3.3 Flow Rate from Drystack Tailings Facility Flow-through Drain

The flow rate from DSTF flow-through drain is monitored at Liese Creek Flume #1 upstream of the RTP (see Figure 4). Liese Creek Flume #1 was installed in April 2013. A pressure transducer is installed during summer season to monitor the water level every hour. The data is downloaded from the pressure transducer by Environmental Staff monthly, and this information is used to evaluate the water balance of the RTP along with the flows recorded by flow meters placed throughout the system.

### 3.3.4 Liese Creek Flow Downstream of Seepage Collection Wells

Liese Creek flow downstream of the SCWs is monitored at Liese Creek Flumes #2, #3, and #4, installed in April 2013 (see Figure 1). A pressure transducer is installed during the summer season to monitor the water level every hour. The data is downloaded from the pressure transducer by the Environmental Department monthly.

### 3.3.5 Dam Crest Elevation

Two survey monuments were established on the dam crest in 2010. The elevation of these monuments is surveyed each spring and fall by the mine surveyors. The initial survey was conducted in September 2010 with results as follows:

- Center monument: 2,089.920 ft
- Spillway side monument: 2,091.682 ft

Environmental staff should ensure that surveyors use consistent methodology when measuring the monuments. When possible, the survey should be completed by a Pogo surveyor who is familiar with the RTP Dam and its survey history. Environmental staff should compare all survey results with past survey results to determine the extent and trend of variance in the elevation readings. Particular attention should be given to unusual survey results or survey results that fall outside of the historical range. Repeat surveying may be necessary to determine whether survey variance represents actual change or variation from survey methodology.

### 3.3.6 Groundwater Monitoring Wells

Two groundwater monitoring wells (MW11-001A, MW11-001B) were constructed between the DSTF and RTP in 2011 to monitor the groundwater down gradient of DSTF. Three groundwater monitoring wells (MW12-500, MW12-501, MW12-502) were constructed in 2012 and four additional monitoring wells (MW18-001, MW18-002, MW18-003A, and MW18-003B) were constructed in 2018 approximately 450 feet downstream of the RTP Dam toe. These wells are sampled and compared with baseline conditions and permit trigger limits. More details on groundwater monitoring are described in the Pogo Mine Monitoring Plan (PGO-ENV-011-PLA).

Prepared by:	James Meyers	Document Status:	Uncontrolled	Document No:	PGO-ENV-008-MAN
Approved by:	Senior Environmental Coordinator	Review Date:	7 Jul 2023	Revision No:	8
		Approver's Signature:	James Meyers	Issue Date:	13 Oct 2023
				Page No:	9

### 3.3.7 Meteorological Stations

Two Meteorological (Met) Stations were constructed at Pogo in 2011, one on Pogo Ridge and the other at the Pogo Airstrip area. Their purpose is to collect data to support air quality and hydrologic modeling. Each station has a ten-meter guyed tower with a two foot by two-foot concrete base pad. The Datalogger™ system is placed in a weatherproof enclosure at the base of each tower. Each station measures the following parameters:

- Wind Speed (m/s) (at 10-meters);
- Wind Direction (degrees) (at 10-meters);
- Sigma Theta (degrees);
- Air Temperature and vertical temperature difference (degree C) (at 2 meters and 10 meters elevation);
- Solar Radiation (W/m<sup>2</sup>);
- Barometric Pressure;
- Heated Precipitation gauge with wind shield (inches); and
- Evaporation rate (Airstrip station only)


Each of the monitoring stations is powered by electrical service with a backup battery and solar power system. Both sites are readily accessible by vehicle.

**Table 2: Pogo RTP Dam Monitoring Items**

Items	Location	Frequency	Monitoring
RTP Reservoir water level and volume	RTP pump station	Continuous	Pressure transducer connected to DCS
Seepage collection well pump-up rate	Seepage collection wells	Continuous	Flow meters connected to DCS
Flow rate from DSTF flow-through drain	Liese Creek Flume #1	Hourly	Water level is collected with pressure transducer
Flow rate into Liese Creek downstream of SCWs	Liese Creek Flume #2	Hourly	Water level is measured with pressure transducer
Flow rate into Liese Creek downstream of all RTP appurtenances	Liese Creek Flume #3	Hourly	Water level is measured with pressure transducer
Dam Crest Elevation	Dam crest survey monuments	Twice per year (May and October)	Mine surveyor provides survey results
Groundwater Monitoring Wells (MW11s, MW12s)	MW11-001A, 001B MW12-500, 501, 502	Quarterly	Water samples are collected by environmental staff
Groundwater Monitoring Wells (MW18s)	MW18-001, MW18-002, MW18-003A, MW18-003B	Monthly (MW18-001), Quarterly	Water samples are collected by environmental staff
Met Stations	Pogo Ridge & Airstrip Area	Hourly	Wind speed and direction, air temp, solar radiation, precipitation


Prepared by:	James Meyers	Document Status:	Uncontrolled	Document No:	PGO-ENV-008-MAN
Approved by:	Senior Environmental Coordinator	Review Date:	7 Jul 2023	Revision No:	8
		Approver's Signature:	James Meyers	Issue Date:	13 Oct 2023
				Page No:	10

Figure 4: Pogo RTP Dam monitoring




Prepared by:	James Meyers	Document Status:	Uncontrolled	Document No:	PGO-ENV-008-MAN
Approved by:	Senior Environmental Coordinator	Review Date:	7 Jul 2023	Revision No:	8
		Approver's Signature:	James Meyers	Issue Date:	13 Oct 2023
				Page No:	11

Figure 5: RTP Elevation and SCW Flow Rates




Prepared by:	James Meyers	Document Status:	Uncontrolled	Document No:	PGO-ENV-008-MAN
Approved by:	Senior Environmental Coordinator	Review Date:	7 Jul 2023	Revision No:	3
		Approver's Signature:	James Meyers	Issue Date:	13 Oct 2023
				Page No:	12

Figure 6: SCW#5-#8 Pump Rate and RTP reservoir elevation



Prepared by:	James Meyers	Document Status:	Uncontrolled	Document No:	PGO-ENV-008-MAN
Approved by:	Senior Environmental Coordinator	Review Date:	7 Jul 2023	Revision No:	3
		Approver's Signature:	James Meyers	Issue Date:	13 Oct 2023
				Page No:	13

Figure 7: SCW#9 Pump Rate and RTP reservoir elevation



Prepared by:	James Meyers	Document Status:	Uncontrolled	Document No:	PGO-ENV-008-MAN
Approved by:	Senior Environmental Coordinator	Review Date:	7 Jul 2023	Revision No:	3
		Approver's Signature:	James Meyers	Issue Date:	13 Oct 2023
				Page No:	14

## 4. MAINTENANCE

This section summarizes the routine and preventative maintenance activities for the RTP site.

**Table 3:** Action Thresholds

Item	Inspection Frequency	Action Threshold	Recommended Response
Seepage collection well condition and operation	Weekly	Deviation from normal operations	Investigate and contact Pogo Maintenance for repair
Liese Creek Flumes 1-4	Monthly (seasonal)	Erosion or significant change in structure	Investigate and contact Pogo Maintenance for repair
DSTF	Weekly	Erosion or significant change in structure	Investigate and contact Pogo Maintenance for repair
RTP Dam and Abutments	Weekly	Vegetation, subsidence, erosion, collapse, etc	Investigate and contact Pogo Maintenance for repair
Spillway and Abutments	Weekly	Corrosion, damage, or irregularities	Investigate and contact Pogo Maintenance for repair
Diversion Ditch	Monthly (seasonal)	Sumps or ditch damaged or flow restricted	Investigate and contact Pogo Maintenance for repair
Dam Crest Monuments	Twice per year (May/October)	Review all results	Compare survey readings with historical trends, request a second survey if results deviate significantly

### 4.1 Dam and Abutments

The dam and abutments are inspected weekly. Any vegetation on the dam and abutments is cleared, and obstacles such as wood debris in the pond are removed if possible.

### 4.2 Spillway

The spillway is inspected during the weekly inspection and after any spill event. The inspection includes checks for signs of corrosion, irregularities in the spillway profile, damage from ice or rocks, and signs of piping along the flume outfall. Any damage to the structure will be repaired. Inspection information is input into Pogo's INX database.

Debris or rocks that fall into the spillway conduit are removed. Prior to the spring freshet, major ice accumulation within the spillway is mechanically or steam cleared if needed.

### 4.3 Diversion Ditch

Major aufeis accumulation in the diversion ditches is managed each spring prior to the freshet. The objective is to provide the proper flow path for the freshet, so that the ice will naturally thaw in the proper locations. It is imperative to keep the water flow within the ditches and off the adjacent access road.

The diversion ditch is inspected monthly and after rain events, in accordance with the Pogo Storm Water Pollution Prevention Plan (SWPPP) (PGO-ENV-020-PLA). SWPPP inspections include removing debris from the diversion ditches as needed.

### 4.4 Seepage Collection Wells

Environmental staff is responsible for weekly visual inspection of the seepage well pump controllers and flow meters. Any deviation from normal operations will be brought to the attention of the Maintenance Department.

There is no requirement for routine maintenance for the seepage collection pumps by the manufacture. The pumps are exchanged when a malfunction occurs.

### 4.5 RTP Pumps, Head Tank and Affiliated Facilities

Mill Department is responsible for daily inspection of the RTP pumps, head tank, and affiliated facilities. Any deviation from normal operations will be brought to the attention of the Maintenance Department.

There is no requirement for routine maintenance for the RTP reclaim pumps by the manufacture. The pumps are exchanged when any malfunction occurs.

Prepared by:	James Meyers	Document Status:	Uncontrolled	Document No:	PGO-ENV-008-MAN
		Review Date:	7 Jul 2023	Revision No:	8
Approved by:	Senior Environmental Coordinator	Approver's Signature:	James Meyers	Issue Date:	10 Oct 2023
				Page No:	15

## 4.6 Liese Creek Flumes

Environmental staff is responsible for bi-monthly visual inspection of the Liese Creek Flumes during the summer season. The accumulated sediments in the flumes are removed by hand. There is no requirement for routine maintenance for the Liese Creek Flumes.

## 5. INSPECTION

**Table 4: Inspection Requirements**

Facility	Frequency	Responsible	Remarks
Seepage Collection Wells	Weekly	Environmental Department	Check controller and flow meters
RTP Head Tank	Daily	Mill Department	Check controller and flow meters
Liese Creek Flumes	Monthly (seasonal)	Environmental Department	Check erosion, sediment accumulation, etc.
RTP Dam and DSTF	Weekly	Environmental Department	Check housekeeping and general conditions, erosion, subsidence, vegetation, and spillway condition
Diversion Ditches & Sumps	Monthly (seasonal)	Environmental Department	Check erosion, sediment accumulation, aufeis accumulation, etc.

### 5.1 Daily Inspection

The RTP Head Tanks are inspected daily by Mill staff. Staff check pump operations, tank levels, and flow rates and record values in Pogo's DCS database.

### 5.2 Weekly Inspection

The RTP Dam and DSTF are inspected visually by the environmental staff on a weekly basis. This includes visual inspection of the seepage collection well system. Staff check pump operations and flow rates. The inspection form is attached in Appendix II. The inspection results are entered into Pogo's INX database.

Table 3 summarizes the requirements of visual inspection.

### 5.3 Monthly Inspection

The North and South Diversion Ditches are inspected visually by environmental staff on a monthly basis when access is not blocked by snow. The inspection form is attached in Appendix II. The inspection results are entered into Pogo's INX database.

### 5.4 Periodic Safety Inspection

A PSI must be performed every three years as required by 11 AAC 93.159. A PSI must be performed by a qualified engineer. Prior approval of the engineer and the scope of the inspection must be agreed upon in advance with the Alaska Department of Natural Resources (ADNR). The draft PSI report shall be submitted to ADNR within 30 days after the visual inspection of the dam.

## 6. EXERCISES

### 6.1 Orientation Exercise

Special Condition #6 of the 2022 *Certificate of Approval to Operate a Dam* requires Pogo to maintain an Emergency Action Plan (EAP) for the RTP Dam. In accordance with Special Condition #6 and the EAP, an annual orientation exercise is conducted to keep responsible parties informed about the EAP.

The Environmental Department is responsible for facilitating the annual orientation exercise with Senior Management and other relevant parties.

### 6.2 Table-top Exercise

Table-top exercises are all-department simulations of Pogo's response to an RTP emergency scenario. Pogo staff simulate a response to the emergency based on guidance from the EAP and Pogo's Crisis Management Plan.

The Environmental Department is responsible for holding the table-top exercises with Senior Management and other relevant parties in collaboration with the Safety department. The first table-top exercise was held in 2011 and is conducted every three years thereafter. Table-top exercises were held in 2014, 2017, 2019, and 2022, with the next exercise planned for 2025.

Prepared by:	James Meyers	Document Status:	Uncontrolled	Document No:	PGO-ENV-008-MAN
		Review Date:	7 Jul 2023	Revision No:	8
Approved by:	Senior Environmental Coordinator	Approver's Signature:	James Meyers	Issue Date:	10 Oct 2023
				Page No:	16



## 7. UNUSUAL OCCURENCES

Unusual occurrences identified in this section include:

- Earthquake
- Extreme precipitation
- High water level

### 7.1 Earthquake

If an appreciable earthquake event occurs (strong enough to be felt by site personnel), site personnel will inspect the Pogo RTP Dam site, including the dam, spillway, diversion ditch, and SCWs, and Mill Department will inspect the RTP reclaim pumps and Head Tank. Any deviation from normal operations will be reported to the Environmental Manager.

### 7.2 Extreme Precipitation

Extreme rainfall is defined as rainfall exceeding two inches in 24 hours. Rainfall information for Pogo Mine site can be obtained from either of Pogo's two meteorological stations using the following links:

- Pogo Mine Ridge Station: <https://app.konectgds.com/kiosk/5ab11367-6ca4-41d6-9dbf-58d16558d59f>
- Pogo Mine Airstrip Station: <https://app.konectgds.com/Kiosk/3af0c101-d047-4855-944c-977c7cdd7dd4>

During these types of rainfall events, the pond condition will be observed, and the spillway inspected to make sure it is clear of debris.

### 7.3 High Water Level

If the reservoir elevation exceeds the elevation of spillway floor (2,080.5 feet amsl), Tier 1 response actions will be activated in accordance with the approved Pogo Mine EAP (PGO-ENV-017-PLA).

## 8. RELATED DOCUMENTS

Document Name	Document Number
Pogo Mine Monitoring Plan	PGO-ENV-011-PLA
Pogo Storm Water Pollution Prevention Plan (SWPPP)	PGO-ENV-020-PLA
Pogo Mine EAP	PGO-ENV-017-PLA

## 9. REFERENCES

- ADEC, 2012, Waste Management Permit # 2011DB0012
- ADNR, 2005, Guidelines for Cooperation with the Alaska Dam Safety Program
- AECOM, 2019, Periodic Safety Inspection Report No. 5 Recycle Tailings Pond Dam
- AMEC, 2004, RTP Dam Design Report
- AMEC, 2006, RTP Dam 2004-2005 As-built Report
- AMEC, 2011, Pogo RTP Dam Second Periodic Safety Inspection Report
- Pogo, 2020, Emergency Action Plan for the Pogo RTP Dam
- Pogo, 2020, Pogo Mine Monitoring Plan
- SRK, 2011, Pogo Mine RTP Dam Break Analysis
- SRK, 2013, Pogo Mine – RTP Dam Spillway and Associated Discharge Structures Verification
- SRK, 2013, DSTF Diversion Ditches Design Calculations
- Teck-Pogo, 2002, Pogo Project Water Management Plan
- U.S. Department of the Interior Bureau of Reclamation, 2001, Water Management Manual

## 10. APPENDICES

Appendix I – Pogo RTP Dam Project Data Sheet

Appendix II – Inspection Forms

Appendix III – Drawings

- RTP Spillway Discharge Capacity
- Pogo Mine Water Treatment Plant #3 Exterior Pipeline – 1875 Portal to RTP Tanks
- RTP Piping & Instrumentation Diagram

Prepared by:	James Meyers	Document Status:	Uncontrolled	Document No:	PGO-ENV-008-MAN
		Review Date:	7 Jul 2023	Revision No:	8
Approved by:	Senior Environmental Coordinator	Approver's Signature:	James Meyers	Issue Date:	10 Oct 2023
				Page No:	17



**POGO RECYCLE TAILINGS POND (RTP) DAM  
PROJECT DATA SHEET**

**RESERVOIR**

Normal Water Surface Elevation: 2,042 feet amsl  
 Normal Storage Capacity: 14.3 acre-feet  
 Maximum Water Surface Elevation: 2,084 feet amsl (spillway crest elevation)  
 Maximum Storage Capacity: 133.2 acre-feet  
 Max. Surface Area at Spillway Crest: 5 acres (approx.)

**HYDROLOGY**

Drainage Basin Area: 0.19 square miles (new diversion ditches system)  
 Average Annual Rainfall: 19 inches  
 100 Year/24 Hour Rainfall: 4.3 inches  
 100 Year Flood: 112 cubic feet per second  
 Probable Maximum Precipitation: 11 inches  
 Flood of Record: 1.88 inches in 21 hours on June 2, 2006  
 Probable Maximum Flood: 473 cfs (SRK 2013)  
 Floods of Record: 1.88 inches in 21 hours on 22 June 2006 (AMEC 2011)  
 1.45 inches in 2 hours on June 10, 2017 (Sumitomo 2017)  
 Inflow Design Flood: 473 cfs

Prepared by:	James Meyers	Document Status:	Uncontrolled	Document No:	PGO-ENV-008-MAN
		Review Date:	7 Jul 2023	Revision No:	8
Approved by:	Senior Environmental Coordinator	Approver's Signature:	James Meyers	Issue Date:	10 Oct 2023
				Page No:	19

## 10.2 APPENDIX II – Weekly and Monthly Inspection Forms

Reference No: 273312



### Inspections - Pogo Checklist

#### PGO - ENV - RTP Dam & Dry Stack Weekly Inspection - PGO - ENV - RTP Dam & Dry Stack Weekly Inspection

Prompt	Yes	No	N/A	Explanation	Comments
Date of inspection:	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		<input style="width: 100%;" type="text"/>
Seepage Collection Wells	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Are all pumps running in Auto Mode? Do the well motor speeds and water levels indicate that the wells are working properly?	<input style="width: 100%;" type="text"/>
RTP Dam	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Are dam faces free of vegetation, erosion, collapse, subsidence? Is downstream dam free of seepage? Is dam crest free of subsidence and damage to facilities? Are reservoir walls free of erosion and collapse? Are dam abutments (north and south) free of erosion and seepage?	<input style="width: 100%;" type="text"/>
Spillway Inlet (Concrete) and Outfall (Flume)	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Is spillway inlet (concrete) free of new cracks and properly connected to flume (culvert)? Are existing cracks stable? Have any new cracks formed? Is spillway outfall (flume) free of damage, obstacles and erosion on the ground? Are spillway abutments (north and south) free of erosion and seepage?	<input style="width: 100%;" type="text"/>
Drystack	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	is the dry stack free of unusual cracks and signs of settlement? is the dry stack free of bulging and seepage? Is the dry stack free of erosion, rills, and gullies? Are 2% slopes being maintained?	<input style="width: 100%;" type="text"/>
Describe and document any maintenance activities completed in response to deficiencies noted in previous inspections.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Notes:	<input style="width: 100%;" type="text"/>
Any unusual events? Describe and document dam performance. (Seismic, weather, etc.)	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Notes:	<input style="width: 100%;" type="text"/>

Prepared by:	James Meyers	Document Status:	Uncontrolled	Document No:	PGO-ENV-008-MAN
		Review Date:	7 Jul 2023	Revision No:	8
Approved by:	Senior Environmental Coordinator	Approver's Signature:	James Meyers	Issue Date:	10 Oct 2023
				Page No:	20



## Inspections - Pogo Checklist

### PGO - ENV - Liese Creek Flume Monthly Inspection - PGO - ENV - Liese Creek Flume Monthly Inspection

Prompt	Yes	No	N/A	Explanation	Comments
Date of inspection:	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		<input style="width: 100%;" type="text"/>
Diversion Ditch Headwall / Sump - North & South	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Does the sump need sediment removed? Are there any operational issues present (excessive vegetation, erosion, overflow, blockage, channel migration away from the headwall / sump)? Any maintenance required?	<input style="width: 100%;" type="text"/>
Diversion Ditches - North, South (Upper), South (Lower)	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Are Diversion ditches free of obstacles and damage? Are diversion ditches free of erosion, sediment accumulation, aufeis, obstacles, and damage?	<input style="width: 100%;" type="text"/>
Flume #1 Dry stack Toe	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Has debris / sediment been cleared from the flume? Is the flume free of erosion and settling? Has the stilling well been flushed? Download / calibrate data logger. Inspect desiccant for data logger, replace if pink. Note the manual weir reading in the comments.	<input style="width: 100%;" type="text"/>
Flume #2 South Diversion Ditch Return (below Seepage Collection Wells)	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Has debris / sediment been cleared from the flume? Is the flume free of erosion and settling? Has the stilling well been flushed? Download / calibrate data logger. Inspect desiccant for data logger, replace if pink. Note the manual weir reading in the comments.	<input style="width: 100%;" type="text"/>
Flume #3 North Diversion Ditch Return	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Has debris / sediment been cleared from the flume? Is the flume free of erosion and settling? Has the stilling well been flushed? Download / calibrate data logger. Inspect desiccant for data logger, replace if pink. Note the manual weir reading in the comments.	<input style="width: 100%;" type="text"/>
Flume #4 Liese Creek (Rd. 7)	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Has debris / sediment been cleared from the flume? Is the flume free of erosion and settling? Has the stilling well been flushed? Download / calibrate data logger. Inspect desiccant for data logger, replace if pink. Note the manual weir reading in the comments.	<input style="width: 100%;" type="text"/>


Prepared by:	James Meyers	Document Status:	Uncontrolled	Document No:	PGO-ENV-008-MAN
Approved by:	Senior Environmental Coordinator	Review Date:	7 Jul 2023	Revision No:	8
		Approver's Signature:	James Meyers	Issue Date:	10 Oct 2023
				Page No:	21

Prompt	Yes	No	N/A	Explanation	Comments
Describe and document any maintenance activities completed in response to deficiencies noted in previous inspections.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Notes:	
Any unusual events? Describe and document flumes performance during unusual events. (Seismic, weather, etc.)	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Notes:	

Prepared by:	James Meyers	Document Status:	Uncontrolled	Document No:	PGO-ENV-008-MAN
Approved by:	Senior Environmental Coordinator	Review Date:	7 Jul 2023	Revision No:	8
		Approver's Signature:	James Meyers	Issue Date:	10 Oct 2023
				Page No:	22

## 10.3 APPENDIX III - Drawings


- RTP Spillway Discharge Capacity



Prepared by:	James Meyers	Document Status:	Uncontrolled	Document No:	PGO-ENV-008-MAN
		Review Date:	7 Jul 2023	Revision No:	8
Approved by:	Senior Environmental Coordinator	Approver's Signature:	James Meyers	Issue Date:	10 Oct 2023
				Page No:	23

# RECYCLING TAILINGS POND OPERATING AND MAINTENANCE MANUAL


- Pogo Mine Water Treatment Plant #3 Exterior Pipeline – 1875 Portal to RTP Tanks



Prepared by:	James Meyers	Document Status:	Uncontrolled	Document No:	PGO-ENV-008-MAN
		Review Date:	7 Jul 2023	Revision No:	8
Approved by:	Senior Environmental Coordinator	Approver's Signature:	James Meyers	Issue Date:	10 Oct 2023
				Page No:	24



- RTP Piping & Instrumentation Diagram



Prepared by:	James Meyers	Document Status:	Uncontrolled	Document No:	PGO-ENV-008-MAN
Approved by:	Senior Environmental Coordinator	Review Date:	7 Jul 2023	Revision No:	8
		Approver's Signature:	James Meyers	Issue Date:	10 Oct 2023
				Page No:	25

The latest version of this controlled document is available on the Document Control Server as a "PDF" file recorded by the Document No. This document is uncontrolled in hard copy and may only be edited or amended with permission of the document approver.